



Project: Heron Academy
Main Contractor: Quinn London
Main Contractor QS: Joanna Kajdana
Sub Contractor QS: Adam Davis
VO Number: V03
Revision: Revision 2
SI Ref:
Date: 01/09/2025

Temporary Hoarding Works - Provisional Sum		QTY	Unit	Rate (£)	Total
Supply and fit new temporary hoarding out of timber and ply, fixed back to existing blockwork structure.					
Materials					
GENERAL PURP PLYWOOD 2440X1220X12 CE2+ E1 EN636-2 FSC® C014770		18	sheets	£32.70	£588.60
PREMIUM CLS SOFTWOOD STUDDING 75x50 3x2 NOM 2.4M PEFC/16-37-158		60	lengths	£5.13	£307.80
Fixings		1	item	£100.00	£100.00
Labour					
2 men 3 days		6	days	£350.00	£2,100.00
				Total	£3,096.40

Reason for VO:

Not part of contracts works. We have been asked by Quinn to carry out these works to temporarily secure site for the construction works to take place safely on site.

Exclusions:

Painting/decorating, groundworks, gates/doors, feet/bases; we have allowed to fix the timber framework to the existing blockwork.