

Project: Heron Academy Main Contractor: Quinn London Main Contractor QS: Joanna Kajdana Sub Contractor QS: Adam Davis

VO Number: V06 **Revision:** Revision 2

SI Ref:

Date: 08/10/2025

	Date: 08/10/2025			
EPDM to Windows and Ground Foor	QTY	Unit	Rate (£)	Total
Supply and fit 400mm wide Class B fire rated EPDM to all windows and the ground floor level	1700	m	£34.00	£57,800.00
We have allwoed for new EPDM sealing to go over the top of the exisiting EPDM as this will be a lot easier and faster to overseal the exisiting that trying to remove it.				
We have allowed for the EPDM to all window and door openings and to the perimetre of the building at ground level				
Added to REV 2 OF VO6				
Allowance to remove exisiting EPDM, nominal quantity. Exact quantity unknon but we know it wont be to every area as some areas dont have any exisiting EPDM to remove.	1000	m	£14.50	£14,500.00
This is requird because after trying to overlap the exisiting EPDM, it has been established that it is not possible to bond the new EPDM to the exisiting. This means removing the exisiting to install new is the only way to gaurantee that the building is properly sealed and water tight.				
			Total	£72,300.00

Reason for VO:

The exisiting EPDM is not fit for purpose and needs to be resealed to ensure that the building is water tights

Exclusions:

Removing existing EPDM. Access.