



Project: Crowndale House
Main Contractor: GPF Lewis
Main Contractor QS: Dave Hodgson
Sub Contractor QS: Adam Davis
VO Number: V08
Revision: Revision 1
Date: 25/06/2025

Bracketry Work	QTY	Unit	Rate (£)	Total
Red Areas: - Supply and Install Window U shaped brackets to the existing timber. East and South Elevations – Perega report 71004; 5mm Aluminium bracket 63x100x63mm @ 120mm with 5 no. holes Provisionl qty	50	nr	£19.00	£950.00
WT05: - Supply and Install Balcony propping brackets and associated fixings nr required 27 – Perega report 71002 from Page 6; 12mm HDG mild steel brackets 100x200mm @ 150mm with 4 no. holes	27	nr	£64.50	£1,741.50
Fixings	1	item	£350.00	£350.00
			Total	£3,041.50

Reason for VO:
 Not part of contractor works.

Exclusions:
 Access.