



Project: Heron Academy
Main Contractor: Quinn London
Main Contractor QS: Joanna Kajdana
Sub Contractor QS: Adam Davis
VO Number: V08
Revision: Revision 1
SI Ref:
Date: 16/10/2025

Supply of Aluminium Spandrel Panels	QTY	Unit	Rate (£)	Total
Cost to supply only Vitradual 5754 Grade, 3mm, solid colour, 1255 Riddle Grey Includes fabrication for Vitradual into cassette panels The removal of existing panels and installation of the panels are already included in our contract works 1255 Riddle Grey is currently in stock. 4-6 weeks lead time for fabrication of panels and delivery to site. Non-stocked colours are on an 8-12 week delivery lead time + the 4-6 week fabrication lead time.	476	m	£146.75	£69,853.00
Cavity infill barrier, tenmat, 30mm, horizontal; NVFB Cavity infill barriers are required to the back of the cassettes to ensure proper fire compartmentation.	476	m	£24.90	£11,852.40
Mastic for fitting cavity infill barriers to cassettes	1	item	£2,000.00	£2,000.00
			Total	£83,705.40

Reason for VO:

Our contract is based upon removing, retaining and reinstating the original spandrel panels. We have been asked to provide a cost option to supply new spandrel panels if required.

Exclusions:

Carried over from sub-contract works