



Project: Crowndale House
Main Contractor: GPF Lewis
Main Contractor QS: Dave Hodgson
Sub Contractor QS: Adam Davis
VO Number: V12
Revision: Revision 1
SI Ref:
Date: 21/10/2025

Additional Supports to Aluminium Cladding		QTY	Unit	Rate (£)	Total
Cost to supply and fix a new supports to the lintels to fix the aluminium rainscreen cladding system to.					
Labour		12	Days	£350.00	£4,200.00
Materials					
Galvanised angles; 100x100 with with slots an 7mm holes RHS; multiple lengths and quantities to suit requirements.		1	item	£1,635.60	£1,635.60
Brackets		1	item	£217.50	£217.50
Delivery		1	item	£250.00	£250.00
Fixings		1	item	£200.00	£200.00
Structural Engineers Report		1	item	£725.00	£725.00
				Total	£7,228.10

Reason for VO:

The blockwork is not suitable/strong enough for us to hang the cladding from, so we are going to need to build this additional galvanised support system fixed to the lintels to fix the sub-frame to.

Exclusions:

Carried over from sub-contract works